

MTP, LEVEL 2

TEST NUMBER:
1.5

PAGE: 1 OF 1

REFERENCE: Q.703 § 7
STD: Fig. 8; Fig. 9

TITLE: Link State Control – Expected signal units/orders

SUB TITLE:
Normal alignment – correct procedure (FISU)

PURPOSE: To check normal alignment procedure

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT, CPT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link

<-----
1 - 0
 SIOS

1 - 0 SIOS
----->

: start

<-----
1 - 0

SIO

1 - 0 SIO
----->

<-----
1 - 0

SIN

1 - 0 SIN
----->

<-----
1 - 0

FISU

1 – 0 FISU

----->

TEST DESCRIPTION

1.

Start normal alignment procedure.

2.

Check link aligns and enters “In service” state.

3.

Check that “In service” state is maintained.

MTP, LEVEL 2

TEST NUMBER: 1.6

PAGE: 1 OF 1

REFERENCE: Q.703 § 7 STD: Fig. 8; Fig. 9

TITLE: Link State Control – Expected signal
units/orders

SUB TITLE: Normal alignment – correct procedure (MSU)

PURPOSE: To check normal alignment procedure

PRE-TEST CONDITIONS: Link out of service

CONFIGURATION: 1

TYPE OF TEST: VAT


EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link



: start

<-----
1-0 SIO

1-0 SIO
----->

<-----
1-0 SIN

1-0 SIN
----->

<-----
1-0 FISU

1-0 MSU
----->

TEST DESCRIPTION

1.

Start normal alignment procedure.

2.

Check link aligns and enters “In service” state.

3.

Check that “In service” state is maintained.

MTP, LEVEL 2

TEST NUMBER: 1.7

PAGE: 1 OF 1

REFERENCE: Q.703 §§ 7, 10.3 STD: Fig. 9; Fig. 17

TITLE: ink State Control – Expected signal units/orders

SUB TITLE: SIO received during normal proving
period

PURPOSE: To test the response to the reception of an SIO during the normal proving period.

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link

<-----

1 - 0 SIOS

1 - 0 SIOS

----->

: start

<-----

1 - 0 SIO

1 - 0 SIO

----->

<-----

1 - 0 SIN

1 - 0 SIN

----->

1 - 0 SIN (one only)

----->

1 - 0 SIN

----->

<-----

1 - 0

<-----

1 - 0 FISU

TEST DESCRIPTION

1.

Send an SIO at B during normal proving period.

2.

Check that new normal proving period is entered.

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link

<-----
1 - 0 SIOS

1-0 SIOS
----->

: set LPO

: start

<-----
1-0 SIO

1-0 SIO
----->

<-----
1-0 SIN

1-0 SIN
----->

<-----
1-0 SIPO

1-0 FISU
----->

<-----

TEST DESCRIPTION

1.

Check that normal alignment is carried out with PLO set at A.

2.

Check that SIPO is returned when aligned, and that A stays in “processor outage” state.

3.

Repeat test with LPO set at B.

MTP, LEVEL 2

TEST NUMBER: 1.9

PAGE: 1 OF 1

REFERENCE: Q.703 §§ 7, 8
Fig. 8

STD:

TITLE:
units/orders

Link State Control – Expected signal

SUB TITLE:

Normal alignment with PO set (MSU)

PURPOSE:
alignment when PO has been set

To check the response following normal

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link

<-----

1-0 SIOS

1-0 SIOS

----->

: set LPO

: start

<-----

1-0 SIO

1-0 SIO

----->

<-----

1-0 SIN

1-0 SIN

----->

<-----

1-0 SIPO

1-0 MSU

----->

<-----

1-0 SIPO

TEST DESCRIPTION

1.

Check that normal alignment is carried out with LPO set at A.

2.

Check that SIPO is returned when aligned, and that A stays in “processor outage” state.

3.

Repeat test with LPO set at B.

MTP, LEVEL 2

TEST NUMBER:
1.10

PAGE: 1 OF 1

REFERENCE: Q.703 §§ 7, 8
STD: Fig. 8

TITLE:
Link State Control – Expected signal units/orders

SUB TITLE:
Normal alignment with PO set and clear

PURPOSE:
To check the response following normal alignment when PO has been set and cleared

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP A

Link

Link

<-----
1 - 0 SIOS

1 - 0 SIOS
----->

 :
set LPO

 : clear LPO

 : start

<-----
1 - 0 SIO

1 - 0 SIO
----->

<-----
1 - 0 SIN

1 - 0 SIN
----->

<-----
1 - 0 FISU

1 - 0 FISU
----->

TEST DESCRIPTION

1.

Check that normal alignment is carried out.

2.

Check that link aligns and enters “In service” state.

MTP, LEVEL 2

TEST NUMBER:
1.11

PAGE:1 OF 1

REFERENCE: Q.703 §§ 7, 8
STD: Fig. 8

TITLE:

Link State Control – Expected signal units/orders

SUB TITLE:

Set RPO when “Aligned not ready”

PURPOSE:

To check the response following normal alignment when PO has been set

PRE-TEST CONDITIONS:

Link out of service; ability to set PO

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP
B

SP A

Link

Link

<-----

1 - 0 SIOS

1 - 0 SIOS

----->

: set LPO

: set LPO

: start

<-----
1 - 0 SIO

1 - 0 SIO
----->

<-----
1 - 0 SIN

1 - 0 SIN
----->

<-----
1 - 0 SIPO

1 - 0 SIPO
----->

TEST DESCRIPTION

1.

Set LPO at A and B.

2.

Start alignment.

3.

Check that both LPO and RPO after alignment completes.

MTP, LEVEL 2

TEST NUMBER:

12

PAGE: 1 OF 1

REFERENCE: Q.703 §§ 7, 8
STD: Fig. 8

TITLE:

Link State Control – Expected signal units/orders

SUB TITLE: SIOS received when “Aligned not ready”

PURPOSE:

To check the response following normal alignment when PO has been set

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP
B

SP A

Link

Link

<-----
1 - 0 SIOS

1 - 0 SIOS
----->

: set LPO

: start

<-----
1 - 0 SIO

1 - 0 SIO
----->

<-----
1 - 0 SIN

1 - 0 SIN
----->

<-----
1 - 0 SIPO

: stop

1 – 0 SIOS
----->

<-----
1 – 0 SIOS

TEST DESCRIPTION

1.

Soon after alignment completes, A enters “Aligned not ready”.

2.

Before alignment completes, stop command is given at B.

3.

Check that, on reception of SIOS, A enters “Out of service” state.

4.

Repeat test with LPO set at B.

MTP, LEVEL 2

TEST NUMBER:
1.13

PAGE:1 OF 1

REFERENCE: Q.703 §§ 7, 8
STD: Fig. 8

TITLE: Link State Control – Expected signal units/orders

SUB TITLE:
SIO received when “Aligned not ready”

PURPOSE:
To check the response following normal alignment when PO has been set

PRE-TEST CONDITIONS:
Link out of service

CONFIGURATION:
1

TYPE OF TEST:
VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP
A

Link

Link

<-----
1 - 0 SIOS

1 - 0 SIOS
----->

: set LPO

: start

<-----
1 - 0 SIO

1 - 0 SIO
----->

<-----
1 - 0 SIN

1 - 0 SIN
----->

<-----
1 - 0 SIPO

1 - 0 SIO
----->

<-----
1 - 0 SIOS

TEST DESCRIPTION

1.

Soon after alignment completes, A enters “Aligned not ready”.

2.

Before alignment completes at B, SIO is sent to A.

3.

Check that, on reception of SIO, A enters “Out of service” state.

4.

Repeat test with LPO set at B.

MTP, LEVEL 2

TEST NUMBER:
1.14

PAGE:1 OF 1

REFERENCE: Q.703 §§ 7, 8
STD: Fig. 8

TITLE:
Link State Control – Expected signal units/orders

191 **Fascicle VI.9 – Rec. Q.781**

SUB TITLE:

Set and clear LPO when “Initial alignment”

PURPOSE: To check normal alignment with PO set and clear during “Initial alignment”

PRE-TEST CONDITIONS:

Link out of service

CONFIGURATION:

1

TYPE OF TEST:

VAT

EXPECTED SIGNAL UNIT SEQUENCE:

SP B

SP
A

Link

Link

<-----
1-0 SIOS

1-0 SIOS
----->

:
start

<-----
1-0 SIO

1-0 SIO
----->

<-----
1-0 SIN

: set LPO

1-0 SIN
----->

: clear LPO

<-----
1-0 FISU

1-0 FISU
----->

<-----
1-0 FISU

TEST DESCRIPTION

1.

Set LPO at A during “Initial alignment” state.

2.

Check A remains in “Initial alignment” state.

3.

Clear LPO before alignment completes at A.

4.

Check A enters “In service” state after normal alignment.

5.

Repeat the test at B.

