

Sheet1

COSTCODE,C PHA	DESCRIPT,C,50	QTY,N,11	UNIT	MANHO	MATERIAL	LABOR,N
0133012000	SK Structure layout,small size	1.0000	Ea	2.0000	0.0000	70.0000
02060102920	SK Roofing removal,built-up	36.0000	Sf	0.0250	0.0000	0.7000
06110501020	SK Framing rafters,12" oc,2 x 4	18.0000	Sf	0.0170	0.3300	0.5950
06110501030	SK Framing shaft trimmer,2 x 6	56.0000	Sf	0.0170	0.5000	0.5950
06110702140	SK Framing,header,single,2 x 12,6' long	4.0000	Ea	0.6150	6.5000	21.5250
06200104040	SK Exterior trim,casing,douglas fir,1 x 4	20.0000	Lf	0.0400	0.6400	1.4000
07210101000	SK Insul,ceiling,fiberglass,unfaced,3-1/2",R11	80.0000	Sf	0.0090	0.2400	0.2520
07620103221	SK Flashing & trim,aluminum,0.019" thick	22.0000	Sf	0.0570	0.7600	1.9380
07810101420	SK Skylight,translucent panel,2-1/2" thick	25.0000	Sf	0.0800	21.8000	2.7200
09250100400	SK Drywall,1/2" thick,nailed,walls	64.0000	Sf	0.0070	0.3100	0.2450
09250101220	SK Taping & finishing drywall	64.0000	Sf	0.0050	0.0300	0.1750
09920102630	SK Paint walls/ceiling,plaster or gypsum,1 paint	80.0000	Sf	0.0040	0.0700	0.1388
02060101720	SK Demo wood,drywall 2 sides	36.0000	Sf	0.0400	0.0000	1.1200
06110501020	SK Framing shaft,2 x 4	64.0000	Sf	0.0170	0.3300	0.5950

OTHER, TRADE PHASEDESC, C, 16

0.0000 1CAR Skylight
0.0000 1LAB Skylight
0.0000 1CAR Skylight
0.0000 1CAR Skylight
0.0000 1CAR Skylight
0.0000 1CAR Skylight
0.0000 1LAB Skylight
0.0000 1RFR Skylight
0.0000 1RFR Skylight
0.0000 1CAR Skylight
0.0000 1CAR Skylight
0.0000 1PNT Skylight
0.0000 1LAB Skylight
0.0000 1CAR Skylight