H.T. [T40.782] MTP LEVEL 3

TEST NUMBER: 3.20	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 5,	
Fig. 28, Fig. 29, Fig. 30	
}	
TITLE: Changeover	
{	
SUB TITLE: Changeover as compatibility test	
}	
{	
PURPOSE:	
To check the changeover procedure as compatibility	
test	
}	
{	
PRE-TEST CONDITIONS:	
Linkset with two available links	
}	
CONFIGURATION: A	TYPE OF TEST: CPT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

	Link	SP A	Link	SP B
:Start traffic				

	1-1	TRAFFIC
	1-2	TRAFFIC
:Deactivate (MML command or failure)	1-1	{
}		
,		CHANGEO
	1-2	TRAFFIC
:Wait	1	l
:Stop traffic		
{ Note		
In a compatibility test it is impossible to describe precisely		
the exchanges of changeover messages because the description depends of the		
type of deactivation of the link and of the time necessary to detect the		
deactivation.		
TEST DESCRIPTION		
1.	{	
Start traffic to B on links $1 - 1$ and $1 - 2$.		
} 2.	{	
Deactivate link $1 - 1$ and check that the changeover is performed.	· ·	
}		
3. Check that the sequence of changeover messages conforms to one of the	{	
descriptions 3.1 to 3.12. Stop traffic.		
}		
4.	{	
Repeat the test by invoking the different reasons listed in the note in test 3.19.		
}		

Tableau [T40.782], p.

H.T. [T41.782] MTP LEVEL 3

TEST NUMBER: 3.21	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 5,	
Fig. 28, Fig. 29, Fig. 30	
_ }	
TITLE: Changeover	
{	
SUB TITLE: Reception of a changeover order on an available link	
}	
{	
PURPOSE:	
To check the changeover procedure on reception of a COO or	
ECO for a link in service	
_ }	
{	
PRE-TEST CONDITIONS:	
Linkset with two available links	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

MEDDITOE DEQUEITOE.					
	Link	SP A	Link SP E	.	
:Start traffic		,	, ,		
-					_
	1 — 1	TRAFFIC	>		
			<	1 — 1	TRAFFIC
	1 — 2	TRAFFIC	>		
			<	1 — 2	TRAFFIC
			<	1 — 2	 {
COO, SLC 1 — 1					
(FSN corresponding to the last received message)					
}	1 — 2	COA, SLC 1 — 1	>		
		TRAFFIC (from 1 — 1)			
	1 2	Transfer (nom 1 1)		1 — 2	TRAFFIC (fr
:Wait	1	I		ı	
:Stop traffic					
TEST DESCRIPTION					

1.	{
Start traffic to B and C on all the links.	
}	
2.	{
Send a COO from B to A for 1 — 1 on link 1 — 2 and check that the COA	
is received.	
}	
3.	{
Check that the link 1 — 1 becomes unavailable.	
}	
4.	{
Stop traffic and check that the changeover procedure has been performed.	
}	
5.	{
Check that there was no loss of messages, no duplication and no	
missequencing.	
}	
6.	{
Repeat the test but send an ECO (instead of a COO) and check that an	
ECA is received (instead of a COA). Some messages may be lost.	
}	

Tableau [T41.782], p.

H.T. [T42.782] MTP LEVEL 3

```
TEST NUMBER: 4.1

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Changeback within a linkset
}

{
PURPOSE:
To check that the changeback procedure is correctly performed on restoration of a link in a linkset
}

{
PRE-TEST CONDITIONS:
Linkset with one available link (end of test 3.1)
}
```

CONFIGURATION: A	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

		SP A
:Start traffic	Link	
Start traine	1-2	TRAFFIC
:Activate (depending of the deactivation mean previously used)	1-1	{
}	1-2	CBD, SLC 1 — 1
	1-1	TRAFFIC (from 1 –
	1—X	CBA, SLC 1 — 1
	1-2	TRAFFIC
:Wait :Stop traffic		I
TEST DESCRIPTION		
1. Start traffic to B (and C in VAT) on link 1 — 2.	{	
2. Activate the link 1 — 1 and check that it enters the correct in service	{	
state.		
3. Check that a CBD for SLC 1 — 1 is received and that traffic for link 1 — 1 is switched back after a CBA is sent.	{	
} 4.	{	
Stop traffic and check that it has been received correctly, no lost messages, no duplication and no missequencing.		
Continue the test by activating the link 1 — 3, then 1 — 4.	{	
6. As a compatibility test, repeat the test for several reasons chosen	{	
among those listed in test 4.10.		

Tableau [T42.782], p.

H.T. [T43.782] MTP LEVEL 3

TEST NUMBER: 4.2	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 6,	
Fig. 28, Fig. 29, Fig. 31	
}	
TITLE: Changeback	
SUB TITLE: Additional CBA	
{	
PURPOSE:	
To check the actions of the system on reception of an	
additional CBA	
}	
{	
PRE-TEST CONDITIONS:	
Linkset with all links available	
}	

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

		SP A	
	Link	1	
:Start traffic			
	ALL	TRAFFIC	
			<
	ATT	TD A FEIG	<
	ALL	TRAFFIC	<
:Wait		I	<
:Stop traffic			
TEST DESCRIPTION			
	(
1. Start traffic to B and C on all links.	1		
Start traffic to B and C on an iniks.			
2.			
Send an unexpected CBA to A and check that this message is discarded			
without action on the traffic.			
}			
3.	Stop traffic.		

Tableau [T43.782], p.

H.T. [T44.782] MTP LEVEL 3

TEST NUMBER: 4.3	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 6,	
Fig. 28, Fig. 29, Fig. 31	
}	
TITLE: Changeback	
SUB TITLE: Additional CBD	
{	
PURPOSE:	
To check the action of the system on reception of an	
additional CBD	
}	
{	
PRE-TEST CONDITIONS:	
Linkset with all links available	
}	

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

	SP A
Link	
ALL	TRAFFIC
1 — X	CBA, SLC 1 — X
ALL	TRAFFIC
{	
{	
\ {	
	ALL 1—X

Tableau [T44.782], p.

H.T. [T45.782] MTP LEVEL 3

```
TEST NUMBER: : 4.4

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: No acknowledgement to first CBD
}

{
PURPOSE:
To check that a second CBD is sent if the first is not acknowledged
}

{
PRE-TEST CONDITIONS:
Linkset with one available link
}
```

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

```
SP A
                                                                           Link
:Start traffic
                                                                           1 — 2
                                                                                                                                      TRAFFIC
                                                                           1 - 1
                                                                                                                                      :Activate
                                                                                                                                     CBD, SLC 1
                                                                           1 - 2
                                                                                                                                      ||| T4||
                                                                           1 — 2
                                                                                                                                     CBD, SLC 1
                                                                           1 - 1
                                                                                                                                      TRAFFIC (f
TRAFFIC (from 1 — 2,
see note)
                                                                                                                                      TRAFFIC
                                                                           1 - 2
:Wait
:Stop traffic
Note
— B may perform a changeback or not.
TEST DESCRIPTION
                                                                            {
                  Start traffic to B and C on link 1-2.
                                   2.
Activate link 1 — 1 and check that a CBD is received (no CBA in response).
                                                                            {
Check that after T4 a second CBD is received and CBA is sent in response
                           before T5 expires.
                                                                            {
           Check that the traffic is changed back on link 1-1.
                                   5.
  Stop traffic and check that there were no lost messages, no duplication
                         and no missequencing.
                                   6.
                                                                            {
        Check that the duration of T4 is inside the specified range.
```

Tableau [T45.782], p.

H.T. [T46.782] MTP LEVEL 3

```
TEST NUMBER: 4.5

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback
{
SUB TITLE: No acknowledgement of repeat changeback declaration
}

{
PURPOSE:
To check that traffic is changed back after a repeat changeback declaration is not acknowledged
}

{
PRE-TEST CONDITIONS:
Linkset with one available link
}
```

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

```
SP A
                                                                        Link
:Start traffic
                                                                        1 - 2
                                                                                                                                   TRAFFIC
                                                                                                                                   :Activate
                                                                                                                                   CBD, SLC 1 —
                                                                                                                                  || T4|
                                                                                                                                   CBD, SLC 1 —
                                                                                                                                  || T5|
                                                                        1 - 1
                                                                                                                                  TRAFFIC (from
TRAFFIC (from 1 — 2,
see note)
                                                                                                                                   TRAFFIC
:Wait
:Stop traffic
Note
— B may perform a changeback or not.
TEST DESCRIPTION
                                 1.
                                                                         {
                Start traffic to B and C on link 1-2.
         Check that a CBD is received and not acknowledged.
Check that after T4, a CBD is repeated and not acknowledged by a CBA.
     Check that after T5, the traffic is changed back on link 1 - 1.
 Stop traffic and check that there were no lost messages, no duplication
                       and no missequencing.
                                 6.
                                                                         {
      Check that an indication was given by the system (§ 6.2.3,
                              Q. 704).
                                 7.
      Check that the duration of T5 is inside the specified range.
```

H.T. [T47.782] MTP LEVEL 3

```
TEST NUMBER: 4.6

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Simultaneous changeback
}

{
PURPOSE:
To check simultaneous changebacks of traffic onto two links
}

{
PRE-TEST CONDITIONS:
Linkset with one available link (end of test 3.14)
}
```

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

```
SP A
                                                                    Link
:Start traffic
                                                                    1 - 3
                                                                                                                              TRAFFIC
                                                                    1 - 1
                                                                                                                              {
:Activate
(depending of the deactivation mean
                                                                    1 - 2
                                                                                                                              :Activate previou
                                                                    1 - 3
                                                                                                                              CBD, SLC 1-1
                                                                    1 - 3
                                                                                                                             CBD, SLC 1 — 2
                                                                    1 - 1
                                                                                                                             TRAFFIC (from 1
TRAFFIC (from 1 - 3,
see note)
}
                                                                    1 - 2
                                                                                                                              TRAFFIC (from 1
TRAFFIC (from 1 - 3,
see note)
}
                                                                                                                             TRAFFIC
                                                                    1 - 3
:Wait
:Stop traffic
Note 1
— B may perform changebacks or not.
Note 2
— Changeback procedures may be performed in sequence. The traffic
sequence presented here, after the changebacks, is the final situation.
TEST DESCRIPTION
                                                                     {
               Start traffic to B and C on link 1 - 3.
                               2.
          Simultaneously activate links 1 - 1 and 1 - 2.
                               3.
  Check that CBDs are received and CBAs are sent (within T4) for
 1-1 and 1-2 and that the traffic is changed back on links 1-1
                           and 1 — 2.
                                }
                                                                     {
Stop traffic and check that there were no lost messages, no duplication
                      and no missequencing.
```

H.T. [T48.782] MTP LEVEL 3

```
TEST NUMBER: 4.7

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Changeback from several alternative links within a linkset
}

{
PURPOSE:
To check the changeback procedure when it is performed to several links in a same linkset
}

{
PRE-TEST CONDITIONS:
Linkset with one unavailable link (end of test 3.15)
}
```

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	•

```
SP A
                                                                     Link
:Start traffic
                                                                      1 - 2, 3, 4
                                                                                                                               TRAFFIC
                                                                      1 - 1
:Activate
(depending of the deactivation mean previously
used)
}
                                                                     1 - 2
                                                                                                                               CBD, SLC 1 —
                                                                     1 - 3
                                                                                                                               CBD, SLC 1 —
                                                                     1 — 4
                                                                                                                               CBD, SLC 1 — 3
                                                                     1 - 1
TRAFFIC
(from 1 - 2, 3, 4)
TRAFFIC (from 1 — 2, 3, 4,
see note)
}
                                                                     1 - 2, 3, 4
                                                                                                                               TRAFFIC
:Wait
:Stop traffic
{
Note
— B may perform changebacks or not.
TEST DESCRIPTION
                                1.
                                                                      {
      Start traffic to B and C on links 1 - 2, 1 - 3 and 1 - 4.
                                                                      {
Activate link 1-1 and check that a CBD is sent on links 1-2, 1-3
and 1 — 4. Check that each CBD contains a different changeback code.
                                3.
                                                                      {
         Check that the traffic is changed back on link 1 - 1.
      Stop traffic and check that there were no lost messages, no
                 duplication and no missequencing.
```

Tableau [T48.782], p.

H.T. [T49.782] MTP LEVEL 3

```
TEST NUMBER: 4.8

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Changeback from another linkset
}

{
PURPOSE:
To check the changeback procedure when it is performed from another linkset
}

{
PRE-TEST CONDITIONS:
Linksets 1 and 3 unavailable (end of test 3.16)
}
```

CONFIGURATION: B	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

	SP A	SP B	SP C	SP •
	Link	Link	Link	Link
:Start traffic				
	2 — 1, 2	TRAFFIC	>	{
5—1 >				
}		SP D		
				{
6-1 >		CD E		
		SP E	<	ſ
2 — 1, 2 <			\	1
[]	5 — 1	SP D		
,			<	{
2 — 1, 2 <				
}	6 — 1	SP E		
	3 — 2	{	•	•
:Activate				
(depending of the deactivation mean previously used)				
}				
	2 — 1	CBD, SLC 3 — 2 CBD, SLC 3 — 2	>	4 — 1 4 — 1
	2 — 2	CBD, SLC 3 — 2	>	4 — 1
	{			
<	2 2	CDA CLC 2 2		
}	3 — 2	CBA, SLC 3 — 2		
<	{			
\	3 — 2	CBA, SLC 3 — 2		
ſ	CHANGEBACK	$\int CDA, SLC J - 2$		
	2-1,2	TRAFFIC	>	{
5—1 >	, -			(
}		SP D		
				{
6-1 >				
}		SP E		
	<	{		
2 — 1, 2 <				
}	5 — 1	SP D		
	3 — 2	TRAFFIC	{	
>	0 1		CD D	
}	8 — 1>	(from 2 V)	SP D	7 — 1
:Wait		(from 2 — X)		/ — 1
:Wait :Stop traffic				
{ Note				
— After activation of link 3 — 2, CBDs are sent from C to A via B				
and				
acknowledged by A. These messages are not presented to simplify the test				
description.				
}				

1	1
Start traffic to E (and D in VAT).	
Start traine to E (and D in VAT).	
}	
2.	{
Activate link 3 — 2 and check that CBDs are received and that CBAs are	
sent before T4 expires in A.	
}	
3.	{
Check that the traffic is changed back on linkset 3 in accordance with	
the load sharing rules in A.	
}	
4.	{
Stop traffic and check that there were no lost messages, no duplication	
and no missequencing.	
}	

Tableau [T49.782], p.

H.T. [T50.782] MTP LEVEL 3

```
TEST NUMBER: 4.9

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Changeback from two linksets
}

{
PURPOSE:
To check the changeback procedure when it is performed from two linksets
}

{
PRE-TEST CONDITIONS:
Linkset 1 unavailable (end of test 3.18)
}
```

CONFIGURATION: B	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

	SP A Link	SP B Link
:Start traffic	2 - 1	TRAFFIC
5—1>		
2 — 1 <}	5 — 1	TRAFFIC
5—1>	2-2	TRAFFIC
}		
2 — 2 <	5 — 1	TRAFFIC
}	$\frac{3-1}{3-1}$	TRAFFIC
> }	8 — 1>	
>	3-2	TRAFFIC
}	8 — 1> 1 — 2	(
:Activate (depending of the deactivation mean previously used)	1 — 2	ĺ
}		
5 — 1>	2—1	CBD, SLC 1 -
}	2 - 2	CBD, SLC 1 -
5—1>		·
	3 - 1	CBD, SLC 1 -
}	8 — 1>	
>	3-2	CBD, SLC 1 -
}	8 — 1>	
2 — X <	5 1	SIC1 2
}	5—1	SLC 1 — 2
2 — X <}	5—1	SLC 1 — 2
2 — X <		
}	5 — 1	SLC 1 — 2
2 — X <		
}	5 - 1 $1 - 2$	SLC 1 — 2 {
TRAFFIC (from linksets 2 and 3)>		
}	1	
<	1 2	
} TRAFFIC	1-2	{
(from linksets 5, see note)		
}	2 - 1, 2	TRAFFIC
5 — 1>	, -	110 11 110

}	$\begin{vmatrix} 3-1,2 \end{vmatrix}$	TRAFFIC
>	3-1,2	IKAFFIC
}	8—1>	
:Wait		
:Stop traffic		
{		
Note		
— D may perform changebacks or not.		
}		
TEST DESCRIPTION		
1.	{	
Start traffic on linksets 2 and 3 to D.		
}		
2.	{	
Activate the link 1 — 2 and check that CBDs are received and that		
CBAs are sent before T4 expires in A. Check that each CBD has a different		
changeback code.		
}		
3.	{	
Check that the traffic is changed back to link 1 — 2 in accordance with		
the load sharing rules in A.		
}		
4.	\	
Stop traffic and check that there were no lost messages, no duplication		
and no missequencing.		
}		

Tableau [T50.782], p.

H.T. [T51.782] MTP LEVEL 3

```
TEST NUMBER: 4.10

{
REFERENCE: Q.704

§ 6,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Changeback due to various reasons
}

{
PURPOSE:
To check the interface L2-L3
}

{
PRE-TEST CONDITIONS:
Linkset with one available link
(end of 3.19)
}
```

CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

:Start traffic
:Activation due to various reasons (see Note) }
:Wait
:Stop traffic { Note — The object of this test is to check the interface L2-L3 by
provoking a changeback by different means listed in § 3 (Q.704). These reasons are: initial alignment procedure completed with success, processor outage condition has ceased at the remote signalling terminal and management request. }
TEST DESCRIPTION
1.
Start traffic to B and C on link 1 — 2. } 2.
Provoke the activation of the link 1 — 1 (see Note above).
3. Check that the traffic is changed back to $1 - 1$.
Check that the traffic is changed back to 1 — 1.
4.
Stop traffic and check that it has been received correctly. }
5. Repeat the test for each reason.

Tableau [T51.782], p.

H.T. [T52.782] MTP LEVEL 3

```
TEST NUMBER: 4.11

{
REFERENCE: Q.704

§ 6.4,
Fig. 28, Fig. 29, Fig. 31
}

TITLE: Changeback

{
SUB TITLE: Time controlled diversion procedure
}

{
PURPOSE:
To check the correct operation of the time controlled diversion procedure
}

{
PRE-TEST CONDITIONS:
Linksets 1, 2 and 4 unavailable
}
```

CONFIGURATION: B	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

```
SP A
                                                                     Link
:Start traffic
                                                                                                                            TRAFFIC (to
                                                                     3 - 1
<-----
                                                                                                                            TRAFFIC (fro
                                                                     3 - 1
                                                                                                                            TRAFFIC (to
                                                                     3 - 2
<-----
                                                                                                                           TRAFFIC (fro
                                                                     3 - 2
                                                                     2 - 1
| fR
:Activate (depending of the deactivation mean previously used)
                                                                                                                            | T21 |
                                                                     3 - 1, 2
                                                                                                                            {
l fR
TRAFFIC STOPPED
| T3
                                                                     2 - 1
                                                                                                                           TRAFFIC (fro
TRAFFIC (from D, see note 2)
                                                                     3 - 1, 2
                                                                                                                           TRAFFIC
<-----
                                                                                                                           TRAFFIC (fro
                                                                    3 - 1, 2
:Wait
:Stop traffic
Note 1
— If SP A is an STP, a TRA message is also sent from A to B
after activation of link 2 — 1.
Note 2
— B performs the point restart procedure and D on reception of
a TFA for A reroutes its traffic to A. These procedures are not presented
to simplify the test description.
TEST DESCRIPTION
             Start traffic to E (and D in VAT) on linkset 3.
                                2.
                                                                     Activate link 2 — 1.
                               3.
 Check that T21 is started in A, and is stopped on reception of TRA from
                         SP B (see notes).
```

{

Check that traffic on linkset 3 ceased in A and that after expiration T3

traffic diverts to link 2 — 1 in accordance with the load sharing rules	
in A.	
}	
5.	{
Stop traffic and check that there were no lost messages, no duplication	
and no missequencing.	
}	
6.	{
Check that the duration of T3 is inside the specified range.	
}	
7.	{
Repeat the test (in VAT) without sending TRA from B to A and check that	
the time controlled diversion is performed when T21 expires.	
}	

Tableau [T52.782], p.

H.T. [T53.782] MTP LEVEL 3

TEST NUMBER: 5	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 7,	
Fig. 29, Fig. 32	
}	
TITLE: Forced rerouting	
SUB TITLE:	
{	
PURPOSE:	
To check that the system can perform forced rerouting	
}	
{	
PRE-TEST CONDITIONS:	
Linksets 1 and 4 unavailable	
}	

CONFIGURATION: B	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

	Link	SP A
:Start traffic	,	ı
	2-1,2	TRAFFIC
>	3 — 1, 2	TRAFFIC
}	to nd	
}	3—1,2	TRAFFIC (from
>	3—1,2	TRAFFIC
}	{	
(to D and from 2 — 1, 2 to E) }		I
<}	$\begin{vmatrix} 3-1,2\\2-1,2 \end{vmatrix}$	TRAFFIC (from
:Wait		
:Stop traffic		
TEST DESCRIPTION	T .	
1. Start traffic on linksets 2 and 3 to E (and D in VAT).	{	
} 2. Deactivate the linkset 6 and check the sending of a TFP concerning E from B to A.	{	
} 3. Stop traffic and check that the forced rerouting has been performed	{	
correctly, messages may have been lost but not missequenced or duplicated. }		
Check that the traffic to D carried by the linksets 2 and 3 has not been disturbed (no lost messages, no duplication and no missequencing).	{	
5. Check that an indication was given by the system.	{	

Tableau [T53.782], p.

H.T. [T54.782] MTP LEVEL 3

TEST NUMBER: 6	PAGE: 1 of 1
{	•
REFERENCE: Q.704	
§ 8,	
Fig. 29, Fig. 33	
}	
TITLE: Controlled rerouting	
SUB TITLE:	
{	
PURPOSE:	
To check that the system can perform controlled rerouting	
}	
{	
PRE-TEST CONDITIONS:	
Linksets 1, 4 and 6 unavailable (end of test 5)	
}	

CONFIGURATION: B	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:	•	

		SP A		SP B		SP C
	Link		Link		Link	
:Start traffic						

	3-1,2	fR TRAFFIC
}	to D and E	
<}	$\begin{bmatrix} 3 - 1, 2 \\ 2 - 1, 2 \end{bmatrix}$	TRAFFIC (from E
(to D and from 3 — 1, 2 to E)	2-1,2	T6 TRAFFIC
} > }	3—1,2	TRAFFIC
<} :Wait :Stop traffic	3—1,2	TRAFFIC (from E
TEST DESCRIPTION		
1. Start traffic to E (and D in VAT).	{	
Activate the linkset 6 and check the sending of a TFA concerning E from B to A.	{	
3. Stop traffic and check that the controlled rerouting has been performed correctly (for all traffic flows, no lost messages, no duplication and no missequencing).	{	
} 4. Check that the duration of T6 is inside the specified range. }	{	

Tableau [T54.782], p.

H.T. [T55.782] MTP LEVEL 3

```
TEST NUMBER: 7.1.1
                                                         PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Inhibition of a link — available link
PURPOSE:
To check for the correct response when link inhibition is
requested for an available link
}
PRE-TEST CONDITIONS:
Linkset with two available links
CONFIGURATION: A
                                                         TYPE OF TEST: VAT, CPT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

```
Link
:Start traffic
TIME—CONTROLLED CHANGEOVER (see note)
:Wait
:Stop traffic
Note
— A changeover is performed after the inhibition of link 1 — 1 but it is not described in this test which checks only the inhibition procedure.
TEST DESCRIPTION
                                                                   1.
                                       Start traffic to B (and C in VAT) on links 1 - 1 and 1 - 2.
                                                                   2.
                                  Initiate inhibition of link 1 — 1 and check that LIN is received and an
                                                    LIA is received in A within T14.
                                                                   3.
                                    Check that the traffic normally carried by link 1-1 is transferred
                                                              to link 1 — 2.
                                                                    }
                                                                   4.
                                     Check that the link 1 — 1 enters in the "Local inhibiting" state.
                                                                   5.
                                                   Repeat test in the reverse direction.
```

Tableau [T55.782], p.

H.T. [T56.782] MTP LEVEL 3

TEST NUMBER: 7.1.2	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Inhibition of a link - unavailable link	
}	
{	
PURPOSE:	
To check for the correct response when link inhibition is	
requested for an unavailable link	
_ }	
{	
PRE-TEST CONDITIONS:	
Linkset with one available link	
}	
CONFIGURATION: A	TYPE OF TEST: VAT, CPT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

		SP A
:Start traffic	Link	
.Start traine	1-1	TRAFFIC
	$\begin{vmatrix} 1-2 \\ 1-1 \end{vmatrix}$:Request inhibitio
	1-1	LIN, SLC 1 — 2
	1-2	{
:Activate (depending of the deactivation mean previously used)		
}	1-1	TRAFFIC
		TRANTIC .
:Wait		
:Stop traffic		
TEST DESCRIPTION	1	
1.	{	
Start traffic to B (and C in VAT) on link 1 — 1.		
}	ſ	
Request inhibition of link 1 — 2, check the reception of LIN at B and	1	
send LIA in response within T14.		
}		
3.	{	
Check that the inhibition was performed.		
}	1	
Activate link 1 — 2 and check that it stays in inhibited state.	· ·	
}		
5.	{	
Stop traffic and check that it was not disturbed.		
6.	1	
Repeat test in reverse direction.		
}		
I .	1	

Tableau [T56.782], p.

H.T. [T57.782] MTP LEVEL 3

TEST NUMBER: 7.2.1	PAGE: 1 of 1			
{				
REFERENCE: Q.704				
§ 10,				
Fig. 28				
}				
TITLE: Management inhibiting				
{				
SUB TITLE: Inhibition not permitted — local reject on available link				
}				
{				
PURPOSE:				
To check the inhibition procedure in case of local reject				
on an available link				
}				
{				
PRE-TEST CONDITIONS:				
Linkset with one available link				
}				
CONFIGURATION: A	TYPE OF TEST: VAT, CPT TYPE OF SP: AL	L		
MESSAGE SEQUENCE:				

		SP A
Start to St.	Link	
:Start traffic	1-1	TRAFFIC
	$ \begin{array}{c c} 1-1 \\ 1-1 \end{array} $:Request inhibition TRAFFIC
:Wait :Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B (and C in VAT) on link 1 — 1.		
} 2.	{	
Request inhibition of link 1 — 1 and check that this request is not permitted.		
}		
Stop traffic and check that it has not been disturbed.	1	
}		
4.	{	
Repeat the test but modify pre-test conditions as follows: link 1 — 1		
available and link 1 — 2 inhibited by B.		

Tableau [T57.782], p.

H.T. [T58.782] MTP LEVEL 3

TEST NUMBER: 7.2.2	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Inhibition not permitted — local reject on unavailable link		
}		
{		
PURPOSE:		
To check the inhibition procedure in case of local reject		
on an unavailable link		
}		
{		
PRE-TEST CONDITIONS:		
All links unavailable		
}		
CONFIGURATION: A	TYPE OF TEST: VAT, CPT TYPE OF SP: ALL	L
MESSAGE SEQUENCE:		

	Link 1 — 1	SP A :Request inhibition
TEST DESCRIPTION	•	•
Request inhibition of link 1 — 1 and check that it is rejected.	{	

Tableau [T58.782], p.

H.T. [T59.782] MTP LEVEL 3

TEST NUMBER: 7.2.3	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Inhibition not permitted — sending of	
LID	
}	
{	
PURPOSE:	
To check the reject of an inhibition asked on reception of an	
LIN	
}	
{	
PRE-TEST CONDITIONS:	
Linkset with one available link	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	'

	Link	SP A
:Start traffic	1-1	TRAFFIC
	$1 - 1 \\ 1 - 1$	LID, SLC 1 – TRAFFIC
:Wait	1	
:Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C on link 1 — 1.		
} 2. Send an LIN, SLC 1 — 1 from B to A and check the reception of an LID.	{	
} 3. Check that the inhibition is not performed.	{	
} 4. Stop traffic and check that it has not been disturbed.	{	
}		

Tableau [T59.782], p.

H.T. [T60.782] MTP LEVEL 3

TEST NUMBER: 7.2.4	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Inhibition not permitted — reception of LID	
}	
{	
PURPOSE:	
To check the reject of an inhibition asked on sending of	
an LIN	
}	
{	
PRE-TEST CONDITIONS:	
Linkset with two available links	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

	Link	SP A
:Start traffic		'
	1-1,2	TRAFFIC
	$\begin{vmatrix} 1-1\\1-X \end{vmatrix}$:Request inhibit
	1-1,2	TRAFFIC
:Wait		
:Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C on links 1 — 1 and 1 — 2.		
} 2.	{	
Request the inhibition of link 1 — 1 and check the reception of LIN and response with an LID before T14 expires in A.		
}		
Check that the inhibition is not performed.	· ·	
4.	{	
Stop traffic and check that it was not disturbed.		

Tableau [T60.782], p.

H.T. [T61.782] MTP LEVEL 3

```
TEST NUMBER: 7.3.1

{
REFERENCE: Q.704

§ 10,
Fig. 28
}

TITLE: Management inhibiting

{
SUB TITLE: Expiration of T14 — available link
}

{
PURPOSE:
To check that the inhibition procedure asked for an available link is restarted when T14 expires
}

{
PRE-TEST CONDITIONS:
Linkset with two available links
}

CONFIGURATION: A

TYPE OF TEST: VAT TYPE OF SP: ALL

MESSAGE SEQUENCE:
```

```
Link
:Start traffic
                                                                                                            1 - 1
                                                                                                            1 - 2
                                                                                                            1 - 1
                                                                                                            1 — X
| T14
                                                                                                            1 - X
                                                                                                             {
TIME—CONTROLLED CHANGEOVER (see note)
                                                                                                            1 - 2
:Wait
:Stop traffic
{
Note
— A changeover is performed after the inhibition of link 1 — 1 but it is not described in this inhibition test.
TEST DESCRIPTION
                                                                                                             {
                            Start traffic to B and C on links 1 - 1 and 1 - 2.
                                                                                                             {
                    Request the inhibition of link 1 — 1, check that an LIN is received
                                            without response.
                       Check that a new LIN is received after T14 expires and that
                                       an LIA is sent in response.
                                                    }
                                                   3.
                   Check that the inhibition is performed. Stop traffic and check that it
                                           was not disturbed.
                    Repeat the test but without sending of an LIA. Check that after the
                           second expiration of T14 the procedure is stopped.
                                                                                                             {
                       Check that the duration of T14 is inside the specified range.
```

Tableau [T61.782], p.

H.T. [T62.782] MTP LEVEL 3

```
TEST NUMBER: 7.3.2 PAGE: 1 of 1

{
REFERENCE: Q.704

§ 10,
Fig. 28
}

TITLE: Management inhibiting

{
SUB TITLE: Expiration of T14 — unavailable link
}

{
PURPOSE:
To check that the inhibition procedure asked for an unavailable link is restarted when T14 expires
}

{
PRE-TEST CONDITIONS:
Linkset with one available link
}

CONFIGURATION: A TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

	Link	SP A
:Start traffic	1-1	TRAFFIC
	$ \begin{vmatrix} 1-2 \\ 1-1 \end{vmatrix} $:Request inhibi LIN, SLC 1 — {
	1-1	LIN, SLC 1 —
	$ \begin{vmatrix} 1-2 \\ 1-1 \end{vmatrix} $:Activate TRAFFIC
:Wait		l
:Stop traffic TEST DESCRIPTION		
1. Start traffic to B and C on link 1 — 1.	{	
${2}$. Request inhibition of link 1 — 2, check that an LIN is received without	{	
response. Check that a new LIN is received after T14 expires and that an LIA is sent in response.		
3. Check that the inhibition is performed.	{	
4. Activate link 1 — 2 and check that it stays unavailable.	{	
5. Stop traffic and check that it was not disturbed.	{	
} 6. Repeat the test but without sending of an LIA. Check that after the second expiration of T14 the procedure is stopped.	{	
}		

Tableau [T62.782], p.

H.T. [T63.782] MTP LEVEL 3

TEST NUMBER: 7.4	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Additionnal inhibition messages (LIA, LID, LIN)	
}	
{	
PURPOSE:	
To check the action of the system on reception of an	
additionnal LIA, LID or LIN	
}	
{	
PRE-TEST CONDITIONS:	
End of test 7.1.1	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

	Link	SP A
:Start traffic	1-2	TRAFFIC
	1-2	TRAFFIC
	$ \begin{vmatrix} 1 - 1 \\ 1 - 2 \end{vmatrix} $	LIA, SLC 1 — TRAFFIC
:Wait :Stop traffic		
TEST DESCRIPTION		
1. Start traffic to B and C on link 1 — 2.	{	
Start traine to B and C on link 1 — 2. } 2. Send an additionnal LIA and LID on link 1 — 2.	{	
} 3. Check that these messages are ignored without impact on the traffic.	{	
} 4. Send an additionnal LIN on link 1 — 2.	{	
5. Check that an LIA is received in response without impact on the traffic	{	
and that the link 1 — 1 enters in the "Local and remote inhibiting" state.		
6.	Stop traffic.	

H.T. [T64.782] MTP LEVEL 3

```
TEST NUMBER: 7.5

{
REFERENCE: Q.704

§ 10,
Fig. 28
}

TITLE: Management inhibiting

{
SUB TITLE: Inhibition asked by the both ends of a link
}

{
PURPOSE:
To check the action of the system on reception of an LIN
after sending of an LIN
}

{
PRE-TEST CONDITIONS:
Linkset with two available links
}

CONFIGURATION: A

TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

:Start traffic	Link	SP A
.start traine	$\mid 1-1,2$	TRAFFIC
	$\begin{vmatrix} 1-1\\1-X \end{vmatrix}$:Request inhib LIN, SLC 1 —
	1-1	LIA, SLC 1 —
TIME-CONTROLLED CHANGEOVER (see note)	{	
}	1-2	TRAFFIC (fro
:Wait { :Stop traffic Note — A changeover procedure is performed but not described in this inhibition test. }		1
TEST DESCRIPTION		
1. Start traffic to B and C on link 1 — 1 and 1 — 2.	{	
} 2. Request inhibition of link 1 — 1. Check the reception of LIN and response with an LIN.	{	
} 3. Check the reception of an LIA and send an LIA.	{	
4. Check that the inhibition is correctly performed and that the link enters in the < <local and="" inhibiting="" remote="">> state.</local>	{	
} 5. Stop traffic and check that it was not disturbed.	{	

Tableau [T64.782], p.

H.T. [T65.782] MTP LEVEL 3

TEST NUMBER: 7.6.1	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Manual uninhibition of a link — with changeback		
}		
{		
PURPOSE:		
To check for correct restoration when link uninhibition is		
requested by an operator		
}		
{		
PRE-TEST CONDITIONS:		
End of test 7.1.1		
}		
CONFIGURATION: A	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEOUENCE:		<u> </u>

:Start traffic	
	1 — 2
	$ \begin{vmatrix} 1 & -1 \\ 1 & -2 \end{vmatrix} $
CHANGEBACK (See note)	CHANGEB 1 — 1
	1 — 2
:Wait	
:Stop traffic Note	
— A changeback procedure is performed after uninhibition of link 1 — 1 but it is not described in this test which checks only uninhibition	
procedure.	
}	
TEST DESCRIPTION	
1.	{
Start traffic to B and C on link 1 — 2.	
} 2.	ſ
Request uninhibition of link 1 — 1, check the reception of an LUN and	{
response with an LUA inside T12.	
}	
3.	{
Check that the uninhibition is performed and stop traffic.	
}	
4.	{
Check that the traffic was shared on links $1 - 1$ and $1 - 2$ according to the load sharing rules.	
the foad sharing fules.	
5.	{
Check that an uninhibition indication was given by the system.	
}	
6.	{
When B has initiated inhibition (point 5, test 7.1.1), repeat test in	
reverse direction. Check that uninhibition is not possible when it is	
requested by an operation in A.	
	i .

Tableau [T65.782], p.

H.T. [T66.782] MTP LEVEL 3

TEST NUMBER: 7.6.2	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Manual uninhibition of a link — without changeback		
}		
{		
PURPOSE:		
To check manual uninhibition procedure when the uninhibited		
link stays unavailable		
}		
{		
PRE-TEST CONDITIONS:		
End of test 7.1.2 without activation of		
link 1 — 2 (link 1 — 2 deactivated and inhibited)		
}		
CONFIGURATION: A	TYPE OF TEST: VAT, CPT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

Stant Aug (G	Link	SP A
:Start traffic	1-1	TRAFFIC
	$ \begin{vmatrix} 1-2 \\ 1-1 \end{vmatrix} $:Request unin
	1-1	TRAFFIC
:Wait :Stop traffic	!	
TEST DESCRIPTION		
1.	{	
Start traffic B (and C in VAT) on link 1 — 1.		
} 2. Request uninhibition of link 1 — 2 and check that an LUN is received and	{	
that an LUA is sent in response inside T12.		
3.	{	
Check that uninhibition is performed correctly and that link $1-2$ stays unavailable.		
4.	{	
Stop traffic and check that it was not disturbed.		
5.	1	
When B has initiated inhibition (point 6, test 7.1.2), repeat test in		
reverse direction. Check that uninhibition is not possible when it		
is requested by an operator in A.		
}		

H.T. [T67.782] MTP LEVEL 3

```
TEST NUMBER: 7.7

{
REFERENCE: Q.704

§ 10,
Fig. 28
}

TITLE: Management inhibiting

SUB TITLE: Expiration of T12

{
PURPOSE:
To check uninhibition procedure on expiration of time T12
}

{
PRE-TEST CONDITIONS:
End of test 7.1.1
(1 — 1 inhibited by A)
}

CONFIGURATION: A

TYPE OF TEST: VAT TYPE OF SP: ALL

MESSAGE SEQUENCE:
```

•	T	
:Start traffic	Link	SP A
.Start transc	1-2	TRAFFIC
	$\begin{vmatrix} 1-1 \\ 1-2 \end{vmatrix}$:Request un LUN, SLC
T12 		
 }		
	1-2	LUN, SLC
CHANGEBACK (See note)	CHANGEBACK (See note) 1 — 1	TRAFFIC (
	1-2	TRAFFIC
:Wait { :Stop traffic Note — A changeback procedure is performed but not described in this uninhibition test.		ı
TEST DESCRIPTION		
1.	\	
Start traffic B and C on link 1 — 2.		
} 2.	{	
Request uninhibition of link $1 - 1$ and check that an LUN is received.		
3. Check that after expiration of T12, a new LUN is received and acknowledged by an LUA.	{	
} 4.	{	
Check that uninhibition is performed correctly.		
5.	{	
Stop traffic and check it was shared on links 1 — 1 and 1 — 2 according with the load sharing rules and that it was not disturbed.		
with the load sharing fules and that it was not disturbed.		
6. Repeat the test but without sending of an LUA. Check that after the	{	
second expiration of T12 the procedure is stopped and an indication		
is given to the management.		
} 7.	{	
Check that the duration of T12 is inside the specified range.		

H.T. [T68.782] MTP LEVEL 3

TEST NUMBER: 7.8	PAGE: 1 of 1	
{	•	
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Not possible uninhibition		
}		
{		
PURPOSE:		
To check the actions of the system when the uninhibition is		
not possible		
}		
{		
PRE-TEST CONDITIONS:		
Link 1 — 2 unavailable and inhibited and		
link 1 — 1 available		
}		
CONFIGURATION: A	TYPE OF TEST: VAT, CPT TY	PE OF SP: ALL
MESSAGE SEQUENCE:		

		SP A
	Link	
	1 — 1	:Deactivate
	1 — X	:Request uninhibition
TEST DESCRIPTION	•	,
1.	Deactivate link 1 — 1.	
2.	{	
Check that uninhibition is not performed.		
}		

Tableau [T68.782], p.

H.T. [T69.782] MTP LEVEL 3

```
TEST NUMBER: 7.9
                                                        PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Automatic uninhibition of a link
PURPOSE:
To check that the system performs uninhibition procedure
when a point becomes unaccessible
{
PRE-TEST CONDITIONS:
End of test
7.1.1
CONFIGURATION: A
                                                        TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

		Link	SP A
	:Start traffic		
		1-2	TRAFFIC
		1-2	:Deactivate (
		1-1	LUN, SLC 1
	POINT RESTART PROCEDURE IS APPLIED IN A AND B	t	
	(see note)		
	}	1-1	TRAFFIC
			IKAFFIC
İ	:Wait	'	ı
	{ :Stop traffic		
	Note Note		
	— When link 1-1 becomes available, point restart procedure is applied		
	in A and B but it is not described in this inhibition test to simplify the		
	test description.		
ŀ	TEST DESCRIPTION		
ŀ	1.	{	
	Start traffic to B and C on link 1 — 2.		
	}		
	2. Deactivate link 1 — 2 and check that an LUN is received on link 1 — 1 and	{	
	response with an LUA within T12.		
	}		
	3.	{	
	Check that uninhibition is performed and that the traffic is restarted on link $1 - 1$ (see note).		
) (see note).		
	4.	{	
	Stop traffic, some messages have been lost.		
	} 5.	{	
	Repeat the test but without sending of an LUA. Check that after the second		
	expiration of T12 the procedure is stopped, an indication is given to		
	the OMAP and the link $1 - 1$ does not carry traffic.		
1	ſ	1	

Tableau [T69.782], p.

H.T. [T70.782] MTP LEVEL 3

```
TEST NUMBER: 7.10.1
                                                          PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Forced uninhibition of a link — sending of an LFU
PURPOSE:
To check forced uninhibition procedure when a point becomes
unaccessible
}
PRE-TEST CONDITIONS:
Link 1 — 1 available, link 1 — 2 inhibited by B
CONFIGURATION: A
                                                          TYPE OF TEST: VAT | TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

:Start traffic
POINT RESTART PROCEDURE IS APPLIED IN A AND B (see note) $\}$
POINT RESTART PROCEDURE IS APPLIED IN A AND B (see note) }
}
1-2
Wait
{ :Stop traffic Note
— When link 1 — 2 becomes available, point restart procedure is applied in A and B but it is not described in this inhibition test to simplify
the test description.
TEST DESCRIPTION
1. {
Start traffic to B and C on link 1 — 1.
} 2.
Deactivate link 1 — 1 and check the reception of an LFU on link 1 — 2.
Response by an LUN. Check that T13 is stopped and that an LUA is
received.
}
3.
Check that uninhibition is performed and that the traffic is restarted
on link $1-2$ (see note).
} 4.
Stop traffic, some messages have been lost.
}

Tableau [T70.782], p.

H.T. [T71.782] MTP LEVEL 3

TEST NUMBER: 7.10.2	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Forced uninhibition of a link — reception of an LFU		
}		
{		
PURPOSE:		
To check uninhibition procedure on reception of an LFU		
}		
{		
PRE-TEST CONDITIONS:		
Link 1 — 1 available, link 1 — 2 inhibited by A		
}		
CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE::		

St. 44 CC	Link	SP A
:Start traffic	1-1	TRAFFIC
	1-1	LUN, SLC 1 — 2
	CHANGEBACK (see note) 1 — 1	TRAFFIC
	1-1	TRAFFIC
:Wait {		l
:Stop traffic		
Note		
— A changeback is performed but not described in this uninhibition		
test.		
TEST DESCRIPTION		
1.	ſ	
Start traffic to B and C on link 1 — 1.		
} 2. Send an LFU to A on link 1 — 2 and check that an LUN is received	{	
within T13 and acknowledged by an LUA inside T12. } 3.	{	
Check that the uninhibition is performed. } 4.	{	
Stop traffic and check that it was carried on $1 - 1$ and $1 - 2$.		

H.T. [T72.782] MTP LEVEL 3

```
TEST NUMBER: 7.11

{
REFERENCE: Q.704

§ 10,
Fig. 28
}

TITLE: Management inhibiting

SUB TITLE: Expiration of T13

{
PURPOSE:
To check uninhibition procedure when T13 expires
}

{
PRE-TEST CONDITIONS:
Link 1 — 1 available and link 1 — 2 inhibited by
B
}

CONFIGURATION: A

TYPE OF TEST: VAT TYPE OF SP: ALL

MESSAGE SEQUENCE:
```

	Link	SP A
:Start traffic		I
	1-1	TRAFFIC
	$ \begin{vmatrix} 1 - 1 \\ 1 - 2 \end{vmatrix} $:Deactivat
		{
T13 		
į		
}	1-2	LFU, SLC
	1-2	LUA, SLO
	{	, , , ,
POINT RESTART PROCEDURE IS APPLIED IN A AND B (see note in 7.9)		
}	1-2	TRAFFIC
:Wait		
:Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C on link 1 — 1.		
} 2.		
Deactivate link 1 — 1 and check the reception of an LFU. After T13	{	
expires, check the reception of a second LFU and send		
an LUN. Check the reception of an LUA.		
}		
3.	{	
Check that uninhibition is performed correctly.		
} 4.	1	
Stop traffic and check that it has been restarted on link		
1 — 2. Some messages have been lost.		
}		
5.	{	
Repeat the test but without sending an LUN. Check that after the second		
expiration of T13 the procedure is stopped, that an indication		
is given to the OMAP and that the link $1-2$ carries traffic normally		
from A.		
) 6.	{	
Check that the duration of T13 is inside the specified	l l	
range.		
}		

H.T. [T73.782] MTP LEVEL 3

```
TEST NUMBER: 7.12
                                                        PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Additionnal uninhibition messages (LUA,
LUN, LFU)
PURPOSE:
To check the actions of the system on reception of an
additionnal LUA, LUN or LFU
{
PRE-TEST CONDITIONS:
Linkset with two available
links
}
CONFIGURATION: A
                                                        TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

:Start traffic		
Start traine	1 - 1, 2	TRAFFIC
		<
	1 12	TD A EELC
	1-1,2	TRAFFIC
		<
	1 — X	LUA, SLC 1 — 1
	1-1,2	TRAFFIC
		<
	1-X	LUN, SLC 1 — 1
:Wait	'	' '
:Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C on link 1 — 1 and 1 — 2.		
} 2.		
Send an LUA (SLC 1 — 1) on link 1 — 2.	{	
3.	{	
Check that this message has been ignored without impact on the		
traffic.		
} 4.		
Send an LUN (SLC 1 — 1) on link 1 — 2.	{	
Schd dif LOTV (SLC 1 — 1) on link 1 — 2.		
5.	{	
Check that an LUA is received in response without impact on the		
traffic.		
}		
6. Send an LUA (SLC 1 — 1) on link 1 — 2.	{	
Send all LOA (SLC 1 — 1) oil link 1 — 2.		
7.	{	
Check that an LUN is received in response without impact on the		
trafic.		
}	g	
8.	Stop traffic.	

Link

Tableau [T73.782], p.

PS A

H.T. [T74.782] MTP LEVEL 3

TEST NUMBER: 7.13	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Uninhibition at one side after	
test 7.5	
}	
{	
PURPOSE:	
To check uninhibition procedure	
when the inhibition has been	
asked by the two ends of a link	
}	
{	
PRE-TEST CONDITIONS:	
End of test	
7.5	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	-

		SP A
:Start traffic	Link	
.start traine	1-2	TRAFFIC
	$ \begin{array}{c c} 1-1 \\ 1-2 \end{array} $:Request uninhibitio
	1-2	TRAFFIC
:Wait :Stop traffic		
TEST DESCRIPTION		
1. Start traffic to B and C on link 1 — 2.	{	
} 2. Request uninhibition of link 1 — 1. Check that an LUN is received and response with an LUA within T12.	{	
} 3. Check that the link stays inhibited (by B).	{	
} 4. Stop traffic and check that it was not disturbed.	{	
} 5. Repeat test in reverse	{	
direction.		
}		

H.T. [T75.782] MTP LEVEL 3

```
TEST NUMBER: 7.14
                                                         PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Automatic uninhibition after
test 7.5
PURPOSE:
To check automatic uninhibition of a link
when the inhibition has been initiated
by the both ends
PRE-TEST CONDITIONS:
End of test
7.5
CONFIGURATION: A
                                                         TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

		SP A
	Link	
:Start traffic		TD A EDIG
	1-2	TRAFFIC
	1-2	:Deactivate (failur
	$\begin{vmatrix} 1 - 1 \end{vmatrix}$	LFU, SLC 1 — 1
	1-1	LUN, SLC 1 — 1
	1 — 1	LUA, SLC 1 —1
POINT RESTART PROCEDURE IS APPLIED IN A AND B		
(see note in 7.9)		
}		TD A DDIG
	1-1	TRAFFIC
:Wait	1	
:Stop traffic		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C on link 1 — 2.		
}		
2.	{	
Deactivate link 1 — 2 and check that forced uninhibition is requested by the both ends which send LFU.		
}		
3.	{	
Check that LUNs are sent by both ends in response and that LUAs are		
sent for acknowledgement.		
}		
4.	{	
Check that the traffic is restarted on link 1 — 1 and stop traffic.		
uame. 		
j J	1	

Tableau [T75.782], p.

H.T. [T76.782] MTP LEVEL 3

```
TEST NUMBER: 7.15
                                                          PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Automatic uninhibition with two links
inhibited
PURPOSE:
To check the actions of the system when two links
are inhibited and when the third (and last) link is
deactivated
{
PRE-TEST CONDITIONS:
Links 1 — 1 and 1 — 2 inhibited (by A) and
link 1 — 3 available
CONFIGURATION: A
                                                          TYPE OF TEST: VAT | TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

		SP A	
a	Link		
:Start traffic	1 2	TDAEEIC	
	1-3	TRAFFIC	
	1-3	:Deactivate (failure)	1
	1 — X	LUN, SLC 1 — 1	.
	and/or	LUN, SLC 1 — 2	.
	{		
(implementation dependent: at least one link must be			
uninhibited)			
			Ι.
			١.
	{		
POINT RESTART PROCEDURE IS APPLIED IN A AND B			
(see note in 7.9)			
}	1-1	TRAFFIC	Ι.
	and/or	IMATIC	
	1-2	TRAFFIC	
:Wait			
:Stop traffic			
TEST DESCRIPTION	D C (111 2		
1. 2.	Deactivate link 1 — 3.		
Check that at least one LUN is received and acknowledged with			
an LUA.			
}			
3.	{		
Check that the traffic is restarted on linkset 1.			
Some messages have been lost.			
4.	Stop traffic.		

Tableau [T76.782], p.

H.T. [T77.782] MTP LEVEL 3

TEST NUMBER: 7.16	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 10,	
Fig. 28	
}	
TITLE: Management inhibiting	
{	
SUB TITLE: Reception of traffic on an	
inhibited link	
_ }	
{	
PURPOSE:	
To check the actions of the system	
on reception of traffic on an inhibited link	
_ }	
{	
PRE-TEST CONDITIONS:	
Link 1 — 1 inhibited by A,	
link 1 — 2 available	
_ }	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	

	Link	SP A	
:Start traffic	1-2	TRAFFIC	
			<
:Wait		•	,
:Stop traffic			
TEST DESCRIPTION			
1.	{		
Start traffic on link 1 — 1.			
}			
2.	{		
Send traffic from B to A on the inhibited link 1 — 2. Check			
that the messages received in A are normally treated.			
}			
3.	Stop traffic.		

Tableau [T77.782], p.

H.T. [T78.782] MTP LEVEL 3

```
TEST NUMBER: 7.17.1
                                                        PAGE: 1 of 3
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Management
inhibiting test — Normal procedure
PURPOSE:
To check that the system performs
correctly the management inhibiting test
PRE-TEST CONDITIONS:
Link 1-1 inhibited by A,
other links are available
CONFIGURATION: A
                                                        TYPE OF TEST: VAT, CPT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

		SP A	
	Link 1 — X	ı	
fR		{	
LLT, SLC 1 — 1			
ļ <u>!</u>			
122			
l i			
<u> </u> -			
}	> <	.1—X	{
· fR			
LRT, SLC 1—1			
1 722			
1 T23			
j-			
}	4 37		
 fR	1-X	{	
LLT, SLC 1 — 1			
<u> </u>			
	> <	.1—X	{
fR			
LRT, SLC 1 — 1			
l i			
}			
TEST DESCRIPTION			
l. Check that an LLT is periodically sent by A and check (in VAT)	{		
that the duration of timer T22 is inside the specified			
range.			
}			
2.	{		
Check that on the reception of an LRT, no action is taken in A.			
}			
3.	{		
As compatibility test, check that an LRT is periodically sent			
from B to A.			

H.T. [T79.782] MTP LEVEL 3

```
{
TEST NUMBER: 7.17.1 Continued
}

PAGE: 2 of 3

{
REFERENCE: Q.704
§ 10,
Fig. 28
}

TITLE: Management inhibiting

{
SUB TITLE: Inhibit test
procedure — Normal procedure
}

PURPOSE: See page 1

{
PRE-TEST CONDITIONS:
Link 1 — 1 inhibited by B,
other links are available
}

CONFIGURATION: A

TYPE OF TEST: VAT, CPT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

		SP A	
	Link		
	1 — X	{	
fR		`	
LRT, SLC 1 — 1			
T22			
T23			
-			
}	> <	.1 — X	{
fR			
LLT, SLC 1—1			
T22			
-			
}			
,	1-X	{	
fR		,	
LRT, SLC 1 — 1			
LKI, SLC I — I			
}	> <	. 1 — X	{
fR			
LLT, SLC 1—1			
}			
TEST DESCRIPTION			
1.	{		
Check that an LRT is periodically sent by A and, in VAT, check			
that the duration of the timer T23 is inside the specified			
range.			
}			
2.	{		
Check that, on the reception of an LLT, no action is taken			
in A.			
}			
3.	{		
As compatibility test, check that an LLT is			
periodically sent from B to A.			
periodically sent from B to A.			

Tableau [T79.782], p.

H.T. [T80.782] MTP LEVEL 3

PAGE: 3 of 3	
TAGE. 5 01 5	
TYPE OF TEST: VAT, CPT TYPE OF SP: ALL	,
	PAGE: 3 of 3 TYPE OF TEST: VAT, CPT TYPE OF SP: ALL

	SP A		SP B
Link		Link	

```
1—X
1—X
1—X
1 - X
                                                         {
}
| fR
LRT,
| 23
j-
| fR
LRT,
| 23
                                                        {
| fR
LLT, SLC 1 — 1
LC1-1
22
1-
| fR
LLT, SLC 1 — 1
LC 1 — 1
| 22
}
                                                         {
---->
<-----
                                                         {
}
1 — X
1 - X
1 - X
1 - X
                                                         {
}
|fR
LRT, SLC 1-1
| 23
1-
fR
  LRT,
```

```
|
|23
                                                                         {
}
|fR
LLT, SLC 1 — 1
| 22
| LC 1 — 1
|-
|fR
LLT, SLC 1 — 1
| 22
TEST DESCRIPTION
                                  1.
                                                                         {
Check that the LLT and LRT messages are periodically sent from A to B and from B to A.
```

Tableau [T80.782], p.

H.T. [T81.782] MTP LEVEL 3

```
TEST NUMBER: 7.17.2
                                                                  PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Inhibit test procedure — Reception of an LLT or LRT on an
uninhibited link
PURPOSE:
To check the actions of the system on
reception of an LLT or LRT on an uninhibited link
PRE-TEST CONDITIONS:
Link 1 — 1 available
CONFIGURATION: A
                                                                  TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

```
SP A
                                                             Link
                                                             1 - 1
                                                                                                                {
| fR
LFU, SLC 1 — 1
| T13
                                                             {
                                                             .1 - 1
                                                                                                                .LUN, SLC 1 — 1
| fR
LUA, SLC 1-1
                                                             ---->
                                                             1 - 1
                                                                                                                {
LUN, SLC 1 — 1
| T12
                                                             {
                                                             .1-1
                                                                                                                . LUA, SLC 1 — 1
TEST DESCRIPTION
                            1.
                                                             {
Send an LLT from B to A and check that an LFU is received. Then,
        send an LUN and check that an LUA is received.
                                                             {
Send an LRT from B to A and check that an LUN is received. Answer
                       with an LUA.
```

Tableau [T81.782], p.

H.T. [T82.782] MTP LEVEL 3

```
TEST NUMBER: 7.17.3
                                                               PAGE: 1 of 1
REFERENCE: Q.704
§ 10,
Fig. 28
TITLE: Management inhibiting
SUB TITLE: Inhibit test procedure — Reception of an LLT on a link
locally inhibited
PURPOSE:
To check the actions of the system on reception of an LLT on
a link locally (not remotely) inhibited
PRE-TEST CONDITIONS:
Link 1 — 1 inhibited in A,
other links are available
CONFIGURATION: A
                                                               TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:
```

	Link	SP A
fR	1—X	{
LFU, SLC 1 — 1		
 - 	{	
>		
}	.1—X 1—X	LUN, SLC 1 -
TEST DESCRIPTION	<u> </u>	,
1. Send an LLT from B to A and check that an LFU is received as described	{	
above.		

Tableau [T82.782], p.

H.T. [T83.782] MTP LEVEL 3

TEST NUMBER: 7.17.4	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 10,		
Fig. 28		
}		
TITLE: Management inhibiting		
{		
SUB TITLE: Inhibit test procedure — Reception of an LRT on a link		
remotely inhibited		
}		
{		
PURPOSE:		
To check the actions of the system on reception of an LRT		
on a link remotely inhibited		
}		
{		
PRE-TEST CONDITIONS:		
Link 1 — 1 inhibited by B,		
other links are available		
}		
CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: ALL
MESSAGE SEQUENCE:		

	Link	SP A	
	1 — X	{	<
fR LUN, SLC 1 — 1			
T12 -			
-			
}	> <	.1 — X	. LUA, SI
TEST DESCRIPTION			
1.	{		
Send an LRT from B to A and check that an LUN is received			
as described above.			
}			

Tableau [T83.782], p.

H.T. [T84.782] MTP LEVEL 3

TEST NUMBER: 8.1	PAGE: 1 of 1
{	
REFERENCE: Q.704	
§ 11, 12.6,	
Fig. 46A	
}	
{	
TITLE: Signalling traffic flow control	
_ }	
{	
SUB TITLE: Reception of a TFC	
}	
{	
PURPOSE:	
To check the actions of the system on reception	
of a TFC	
}	
{	
PRE-TEST CONDITIONS:	
One or more link	
available	
}	
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF SP: ALL
MESSAGE SEQUENCE:	•

:Start traffic	Link	SP A	
:Start tranic	1-1	TRAFFIC	
			<
:Wait			
:Stop traffic			
{			
Note			
— This test requires further study.			
}			
TEST DESCRIPTION			
1.	Start traffic to B and C.		
2.	{		
Send a TFC concerning C and check that this message is received	•		
correctly.			
}			

Tableau [T84.782], p.

H.T. [T85.782] MTP LEVEL 3

```
TEST NUMBER: 8.2
                                                       PAGE: 1 of 1
REFERENCE: Q.704
§ 11, 12.6,
Fig. 46A
}
TITLE: Signalling traffic flow control
SUB TITLE: Sending of TFCs
PURPOSE:
To check the detection of a level 3
congestion
}
{
PRE-TEST CONDITIONS:
All links
available
CONFIGURATION: C
                                                       TYPE OF TEST: VAT TYPE OF SP: STP
MESSAGE SEQUENCE:
```

	Link	SP B	Li
:Start traffic	1-1	TRAFFIC	(>
	1-2	TRAFFIC	(>
:Wait	·	1 — X	TI
			{
. One TFC each 8 messages sent to C			
· }	<	1 — X	TF
	1-1	TRAFFIC	. (<
	1-2	TRAFFIC	<- (<:
Note — n is the maximum load capacity of linkset 2. The traffic model used in this test is described in Table 2/Q.706. } TEST DESCRIPTION			
Start traffic to C with a load exceeding $n/2$ erlang on links $1-1$ and $1-2$ (n is the maximum load that the link 2 may carry without congestion).	{		
Check that the signalling traffic flow control procedure is started in A. Check that a TFC message concerning C is received for each 8 messages received in B during the congestion.	{		
3. Reduce the load to 0.1 erlang or less on links 1 — 1 and 1 — 2. }	{		
4. Check that the congestion disappears and that no TFC is received.	{		
5. 6. Check that the traffic from C to B has not been disturbed.	Stop traffic. {		

H.T. [T86.782] MTP LEVEL 3

TEST NUMBER: 8.3	PAGE: 1 of 1	
{		
REFERENCE: Q.704		
§ 11.2.7		
}		
{		
TITLE: Signalling traffic flow control		
}		
{		
SUB TITLE: Reception of a UPU		
}		
{		
PURPOSE:		
To check the actions of the system on reception of		
a UPU		
}		
{		
PRE-TEST CONDITIONS:		
One link available		
}		
CONFIGURATION: A	TYPE OF TEST: VAT TYPE OF S	P: see note
MESSAGE SEQUENCE:	•	

	Link
:Star traffic	l 1 1
	$\begin{vmatrix} 1-1\\1-1 \end{vmatrix}$
	1-1
	1-1
:Wait	
:Stop traffic	
{	
Note	
— The impact of the reception of a UPU on the traffic from A to B requires further study. The SPs having user part(s) are	
concerned.	
}	
TEST DESCRIPTION	
1.	{
Start traffic to B and C with SI=X.	
}	
2.	{
Send a UPU from B to C with SI=X.	
}	
3.	{
Check that the UPU message is received correctly without impact on the	
traffic from to A to C.	
}	W 1
4.	Wait and stop traffic.

H.T. [T87.782] MTP LEVEL 3

TEST NUMBER: 8.4	PAGE: 1 of 1	
{	•	
REFERENCE: Q.704		
§ 11.2.7		
}		
{		
TITLE: Signalling traffic flow control		
}		
SUB TITLE: Sending of a UPU		
{		
PURPOSE:		
To check the detection of an unavailability of a user		
part		
}		
{		
PRE-TEST CONDITIONS:		
One link available		
}		
CONFIGURATION: A	TYPE OF TEST: VAT	TYPE OF SP: See note
MESSAGE SEOUENCE:	•	

		I CD A
	Link	SP A
:Start traffic	1-1	{
TRAFFIC		1
(to B and C, SI=X)		
}	>	
TRAFFIC		
(from B and C, SI=X)		
}		{
:Deactivate user part X (see note)		
}		
MESSAGE		
(from B to A, SI=X)		
}		
	1-1	UPU (DPC =
MESSAGE		
(from C to A, SI=X)		
}	1-1	UPU (DPC =
		ore (bre=
MESSAGE		
(from B to A, SI=X)		
}	1-1	UPU (DPC =
		:Reactivate us
TRAFFIC		
(from B and C to A, SI=X)		
}		
TRAFFIC	1-1	{
(to B		
and C, SI=X)		
} :Wait	>	
:Stop traffic		
{		
Note — The notion of unavailability of a user part is specific to the		
implementation, consequently, the ability to deactivate a user part is		
implementation dependent. The SPs having user part(s) are		
concerned.		
TEST DESCRIPTION		
1.	{	
Start traffic to B and C with $SI = X$.		
} 2.	Deactivate the user part X.	
3.	{	
Send a message from B to the user part X in A and check that this message		
is discarded and that a UPU is sent back.		
4.	{	
Send a message from C to the user part X in A and check that this message		
is discarded and that a UPU is sent back.		
) 5.	{	

Repeat point 3 and reactivate the user part.	
}	
6.	{
Check that the messages sent from B and C are received correctly and that	
no UPU is sent back. Wait and stop	
traffic.	
}	

Tableau [T87.782], p.

H.T. [T88.782] MTP LEVEL 3

```
TEST NUMBER: 9.1.1
                                                           PAGE: 1 of 1
REFERENCE: Q.704
§ 13,
Fig. 29, Fig. 44
TITLE: Signalling route management
SUB TITLE: Sending of a TFP on an alternative route — failure
of normal linkset
{
PURPOSE:
To check the sending of a TFP on the alternative route
when the normal linkset becomes unavailable
PRE-TEST CONDITIONS:
All linksets
available
CONFIGURATION: D
                                                           TYPE OF TEST: VAT, CPT TYPE OF SP: STP
MESSAGE SEQUENCE:
```

-	CD A	CD D
	SP A	SP B
	Link	Link
:Start traffic		
	1-1	TRAFFIC
5—1 >		
}		SP D
		(from nd)
6—1 >		
}		SP E
,	2-1	TRAFFIC (from
>		(
}	7 — 1>	
J	1-1	ſ
:Deactivate		ĺ
(MML command or failure)		
}		
	2-1	TFP, $PC = B$
>		
}		
	2-1	TFP, $PC = D$
>		
}		
,	2-1	TRAFFIC
>		THE HITTE
	7—1>	
}	/—1>	(6 1 1)
TT7 '-		(from 1 — 1)
:Wait		
:Stop traffic		
{		
Note		
— A changeover procedure is performed after deactivation of link		
1 — 1 but it is not described in this transfer prohibited		
test.		
}		
TEGT DECCRIPTION		
TEST DESCRIPTION	I	
1.	{	
Start traffic to D and E on linkset 1 and 2.		
}		
2.	\ {	
Deactivate link 1 — 1 and check that TFPs concerning B and D are sent		
from A to C (alternative route to reach B and D). Check that no TFP		
concerning E is sent from A to C (load sharing between linksets 1 and		
2 in A to reach E).		
}		
3.	{	
Check that time out T8 is started for each		
TFP sent.		
}		
4.	{	
Check that the traffic to D and E is diverted to C.		
check that the traffic to D and E is diverted to C.		
) 5		
5.	{	
Stop traffic and check that it was not		
disturbed.		
1	1	

H.T. [T89.782] MTP LEVEL 3

```
TEST NUMBER: 9.1.2
                                                                PAGE: 1 of 1
REFERENCE: Q.704
§ 13,
Fig. 29, Fig. 44
TITLE: Signalling route management
SUB TITLE: Sending of a TFP on an alternative route — on reception
of a TFP
}
{
PURPOSE:
To check the sending of a TFP on the alternative route when
the normal route becomes unavailable on reception of a TFP
PRE-TEST CONDITIONS:
Linkset 4
unavailable
CONFIGURATION: D
                                                                TYPE PF TEST: VAT, CPT TYPE OF SP: STP
MESSAGE SEQUENCE:
```

```
SP A
                                                                                                                   SP B
                                                              Link
                                                                                                                   Link
:Start traffic
                                                               1 - 1
                                                                                                                   TRAFFIC
5 — 1 | ----->
                                                                                                                   SP D
                                                                                                                   (from | | nd | )
6-1| ---->
                                                                                                                   SP E
                                                               2 - 1
                                                                                                                   TRAFFIC (from
}
                                                               7 — 1 ----->
                                                               5 - 1
                                                                                                                   :Deactivate
                                                               See note
                                                                                                                   <-----
                                                                                                                   TFP, PC = D
                                                               2 - 1
  ---->
                                                               1 - 1
                                                                                                                   TRAFFIC (from |
6-1| ----->
                                                                                                                   SP E
                                                               2 - 1
                                                                                                                   TRAFFIC
   ---->
                                                               8 — 1 ---->
                                                                                                                   {
(from A and F, and from 1 — 1 to D)
                                                               7 — 1 ----->
:Wait
:Stop traffic
{
Note
— A forced rerouting is performed after the reception of TFP for D
in A but it is not described in this transfer prohibited
test.
TEST DESCRIPTION
                             1.
                                                               Start traffic to D and E.
                             2.
  Deactivate link 5 — 1 and check that a TFP concerning D is sent
                             3.
Check that a TFP concerning D is received from A and that traffic to D
                      is diverted via C.
                             4.
                                                               {
               Check that a time out T8 is started.
 Stop traffic and check that traffic to E has not been disturbed. Some
               messages to D may have been lost.
```

Tableau [T89.782], p.

H.T. [T90.782] MTP LEVEL 3

```
TEST NUMBER: 9.2.1
                                                       PAGE: 1 of 1
REFERENCE: Q.704
§ 13,
Fig. 29, Fig. 44
}
TITLE: Signalling route management
SUB TITLE: Broadcast of TFPs — on one linkset
failure
}
{
PURPOSE:
To check the broadcast of TFPs when one point is
inaccessible
PRE-TEST CONDITIONS:
All linksets
available
CONFIGURATION: D
                                                        TYPE OF TEST: VAT, CPT TYPE OF SP: STP
MESSAGE SEQUENCE:
```

	SP A	SP B		
	Link	Link		
:Start traffic				
	3 - 1	{		
TRAFFIC >				
(from A, D and E)				
}				
	3 - 1	{		
:Deactivate				
(MML command or failure)				
}				
	1 - 1	{		
TFP, PC = F >				
}				
	2 - 1	{		
TFP, PC = F >				
}				
:Wait				
:Stop traffic				
{				
Note				
— The propagation of TFPs is not presented to simplify the test				
description.				
}				
TEST DESCRIPTION				
1.	Start traffic to F.			
2.	{			
Deactivate link 1 — 1 and check that TFPs concerning F are				
broadcasted.				
}				
3.	{			
Check that a timer T8 is started.				
}				
4.	Stop traffic.			

Tableau [T90.782], p.