

Sheet1

COSTCODE,C PHA	DESCRIPT,C,50	QTY,N,11,	UNIT	MAN	HO	MATERIAL
01330120000	PA Structure layout,small size	1.0000	Ea	2.0000		0.0000
01330730000	PA Final cleanup & demobilization,small project	1.0000	Lot	4.0000		0.0000
02220901020	PA Hand excavation,avg soil,2' deep	2.0000	Cy	0.8890		0.0000
02226201000	PA Fill,gravel,hand spread,compact,6" deep	150.0000	Sf	0.0100		0.2150
03110251020	PA Job built,equipment pad forms,1 use	12.0000	Sf	0.1000		2.1000
03210251000	PA Reinforcing,equipment pad,#3-#4	0.0500	Ton	16.0000		638.0000
03380551030	PA Place concrete,slab/mat,2500#,by buggy	2.2500	Cy	0.5330		56.5000
04441101000	PA Flagstone,irregular shapes,1" thick	150.0000	Sf	0.2000		1.7500

LABOR,N,OTHER,TRADEPHASEDESC,C,16

70.0000	0.0000	1CAR	Patio
112.0000	0.0000	1LAB	Patio
24.8920	0.0000	1LAB	Patio
0.2800	0.0000	1LAB	Patio
3.5000	0.0000	1CAR	Patio
640.0000	0.0000	1RDM	Patio
14.9240	0.0000	1LAB	Patio
7.0000	0.0000	1BRK	Patio